	مستشفى الخرطوم التعليمي									
	Medical PSA oxygen generator plant 60 m3/hr									
No	**Department/Room**	**No. of O2 Outlets**	**Unit price Euro**	**No. of MA4 Outlets**	**Unit price Euro**	**No. of SA7 Outlets**	**Unit price Euro**	**No. of VAC Outlets**	**Unit price Euro**	**Type of Outlets**
	GND Floor									
1	ICU	44		44				44		Bed Head Unit
2	Asthema	4		4				0		Wall Outlet
3	ER Hot Case	17		0				0		Wall Outlet
4	ER Truma ward	10		0				0		Wall Outlet
5	ER Surgery ward	10		0				0		Wall Outlet
6	OR	8		8		8		8		Wall Outlet
7	Recovery	4		0				4		Wall Outlet
8	Medicine Ward	10		0				0		Wall Outlet
9	BME workshop	1		1				1		Wall Outlet
	1st. Floor									
10	Wards (Surgery & Truma	24		0				0		Wall Outlet
	2nd. Floor									
11	Wards (Surgery & Truma	18		0				0		Wall Outlet
	TOTAL	**150**		**57**		**8**		**57**		
	Description	**Qty.**	**Unit price Euro**	**Total price Euro**						
	AVSU & Alarm 1 Gases	**5**								
	AVSU & Alarm 2 Gases	**1**								
	AVSU & Alarm 3 Gases	**3**								
	AVSU & Alarm 4 Gases	**1**								
	Shut off valve	**64**								
	Accessories for network									
	Bed Head Unit	22								
	Oxygen Flow meter with humidifier DIN standard	100								
	Medical Air probe -A4 DIN standard	35								
	Surgical Air probe -A7 DIN standard	8								
	Oxygen probe DIN standard	44								
	Vacuum flow regulator with DIN probe and collecting jar 1 ltr wall mounted	35								
	Mobile suction trolley collecting jar, 2x2 ltr with DIN probe	6								